

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-20696-00-00
Spot: NENWSW Sec/Twnshp/Rge: 24-32S-32W
2300 feet from S Section Line, 4293 feet from E Section Line
Lease Name: STANLEY Well #: 1-24
County: SEWARD Total Vertical Depth: 5696 feet

Operator License No.: 34089
Op Name: AGRICULTURAL ENERGY SERVICES
Address: PO BOX 31865
EDMOND, OK 73003

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4300		WITH 2 SX CMT
PROD	4.5	5680	1705	WITH 490 SX CMT
SURF	8.625	1693		WITH 550 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 01/19/2016 12:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: MIKE BRADY Company: AGRICULTURAL ENERGY SERVIC Phone: (620) 629-5660

Proposed Plugging Method: CIBP @ 4300' WITH 2 SX CMT. PLUG AT 1710' WITH 50 SX CMT. PLUG AT 450' WITH 40 SX CMT. PLUG AT 40-0' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/19/2016 5:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

CIBP @ 4300' WITH 2 SX CMT. 1ST PLUG AT 1705' WITH 50 SX CMT. WENT ON VACUUM. RAN SAND LIKE IN TAGGED CMT AT 1320'. LOADED HOLE & STAYED. 2ND PLUG AT 472' WITH 40 SX CMT. 3RD PLUG AT 63-0' WITH 20 SX CMT. 5 SX CMT TO TOP OFF.

Perfs:

Top	Bot	Thru	Comments
4346	4350		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed [Signature]

RECEIVED
JAN 21 2016
KCC DODGE CITY

Received (TECHNICIAN)
KANSAS CORPORATION COMMISSION

JAN 29 2016
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

no 2-2-16