

LEASE NAME Taylor

WELL NUMBER 2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 33 TWP. 26 RGE. 13W (E) or (W)

COUNTY Pratt

Date Well Completed

Plugging Commenced 8-22-95

Plugging Completed 8-31-95

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Rama Operating Company, Inc.

ADDRESS P.O. Box 159 Stafford, Ks. 67578

PHONE# (316) 234-5191 OPERATORS LICENSE NO. 3911

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4415'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	810'	none
				5-1/2"	4415'	812'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Plugged off bottom with sand to 3612' and 5 sacks cement. Shot pipe @2000', 1500', 1300', 1200', 812', pulled 25 joints of 5-1/2" casing. Plugged surface with 300# hulls, 5 sacks gel, 50 sacks cement, 15 sacks gel, 100# hulls, released plug, 100 sacks cement, 65/35 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc.

License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

RECEIVED
 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rama Operating Company, Inc.

SEP 21 1995 9-21-95

STATE OF Kansas COUNTY OF Rice

CONSERVATION DIVISION
 Wichita, Kansas

Mike Kelso

(Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 20th day of September, 1995

Irene Herzberg
 Notary Public

My Commission Expires:
 USE ONLY ONE SIDE OF EACH FORM

