


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pratt County, Sec. 33 Twp. 26 Rge. 13 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
150' E NW NW SE  
Lease Owner W. L. Kirkman, Inc.  
Lease Name Lemon #2 Well No. \_\_\_\_\_  
Office Address Wichita, Kansas  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above  
Section Plot

Date Well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 10/8/79 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 10/10/79 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation  
depleted  
If a producing well is abandoned, date of last production  
\_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owens  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3300  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	411	none
				5 1/2"	3272	2881'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Sanded to 3150' and ran 5 sacks cement. Shot pipe at 2990', 2870', pulled 80 joints.  
Squeezed hole with 8 sacks hulls, 25 sacks gel, released plug and displaced with  
200 sacks common cement.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS

SUBSCRIBED AND SWORN TO before me this 19th day of October, 1979

Margaret Melcher  
Notary Public.

My commission expires



RECEIVED  
STATE CORPORATION COMMISSION 10-22-79

OCT 22 1979

CONSERVATION DIVISION  
Wichita, Kansas

KANSAS DRILLERS LOG

COMPANY W. L. Kirkman, Inc.

SEC. 33 26S R. 13W  
LOC 150' E NW NW SE

FARM Lemon

NO. 2

COUNTY Pratt

ROTARY TOTAL DEPTH 3,300'

COMM. October 12, 1978

COMP. October 19, 1978

CONTRACTOR H-30, Inc.

ISSUED October 24, 1978

CASING

10 3/4" Set at 411' cemented w/350 sxs cement

8 5/8"

ELEVATION 1,961 K.B.

5 1/2" Set at 3,272' cemented w/150 sxs cement

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Red Bed

423'

Shale

1,735'

Lime and Shale

3,300'

Rotary Total Depth

3,300'

I hereby certify the above and foregoing to be  
a true and correct log of the above described  
well as shown by the drilling reports.

H-30, Inc.

*Dean Britting*  
Dean Britting

State of Kansas }  
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public  
in and for said county and state this 24th day of  
October, 1978.



*Elsie Willison*  
Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982

4-30-79

RECEIVED  
STATE CORPORATION COMMISSION

APR 30 1979

CONSERVATION DIVISION  
Wichita, Kansas