


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Pratt County, Sec. 25 Twp. 26S Rge. ~~EX~~ 13(W)
Location as "NE/CNW/SW" or footage from lines NW NW NE
Lease Owner Texaco Inc.
Lease Name L. Knop Well No. 4
Office Address 614 Bitting Bldg., Wichita, Ks. 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 3-31-1955
Application for plugging filed (9-12-68 Resubmitted) 3-27-1968
Application for plugging approved 9-13-1968
Plugging commenced 10-8-1968
Plugging completed 10-17-1968
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 10-19-1967
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation Viola Depth to top 4190 Bottom 4205 Total Depth of Well 4355 Feet
Show depth and thickness of all water, oil and gas formations. PB 4230

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Viola	Oil	4190	4205	10-3/4"	582'	None
				7"	4366'	1825'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand from 4230-4180'. Mixed and dumped 5 sx of cmt from 4180-4155'. Pulled casing. Mudded hole to 350'. Set 15' rock bridge from 350-335'. Mixed and dumped 35 sx cmt from 335-265'. Mudded hole from 265-40'. Set 10' rock bridge from 40-30'. Mixed and dumped 15 sx of cmt from 30' to base of the cellar.


RECEIVED
STATE CORPORATION COMMISSION
NOV 21 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Russ Casing Pulling Inc.
Address P. O. Box 1082, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
F. E. Anderson (employee of owner) or (owner or operator) of the above-described well, being first, duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. E. Anderson
614 Bitting Building, Wichita, Kansas
(Address)

Subscribed and sworn to before me this 20th day of November, 1968



Peggy Sue Jones
Notary Public.

My commission expires 10-13-69

OPERATOR: The Texas Company
 L. Knop #4
 NW NW NE Sec. 25-26-13W
 Pratt County, Kansas

CONTRACTOR: Prime Drilling Company
 COMM: 2/18/55
 COMP: 3/10/55

<u>Formation</u>	
Surface hole	40
Sand & Clay	93
Sand	280
Red Bed & Shale	420
Red Bed	583
Shale & Red Bed	720
Sand	1000
Lime & Shells	1065
Shale & Lime Streaks	1500
Shale & Shells	1810
Shale & Lime	1940
Lime & Shale Streaks	2040
Lime & Shale	2830
Shale & Lime Streaks	2015
Lime & Shale	3129
Sand & Shale	3180
Lime	3272
Lime & Shale	3407
Sand & Lime	3525
Lime	3575
Shale	3580
Lime & Sand	3648
Shale & Lime Shells	3745
Lime	3819
Lime & Shale	3900
Broken Lime	3950
Lime	4150
Diamond Core #1	4157
Shale & Lime	4171
Cherty Lime	4174
Lime	4125
Core #3	4257
Core #4	4275
Shale & Lime	4340
Shale & Sandy Lime	4350
Lime	4355
Rotary Total Depth	4355

Remarks
 Set 10-3/4" casing at 581' cemented with 500 sacks cement.

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 13 1968
 CONSERVATION DIVISION
 Wichita, Kansas

Set 7" casing at 4348' cemented with 175 sacks cement and 3% gel.

We certify that the above log is true and correct to the best of our knowledge and belief.

PRIME DRILLING COMPANY

R.R. McNicol
 R. R. McNicol