

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Pratt County. Sec. 25 Twp. 26 Rge. 13 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C E/2 NW/4 NW/4
Lease Owner Beardmore Drilling Company
Lease Name Lunt Well No. 5
Office Address Pratt, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 7-12-66 _____ 19____
Plugging completed 7-18-66 _____ 19____
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4348 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"		
				8-5/8"	380'	None
				5-1/2"	4347'	3206'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, sanded hole to 3875' and dumped 5 sacks of cement @ 3875' with dump bailer. Pulled 5 1/2" casing, set rock bridge @ 350' and dumped 8 sacks of cement. Ran 30' of sand and dumped 5 sacks of cement. Bailed hole down and dumped 20 sacks of cement. Mudded hole to 40', set rock bridge and capped well with 10 sacks of cement.

8-2-66

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

AUG 2 1966

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of July, 1966

My commission expires May 20, 1968

Milton J. Volin
Notary Public.

BEARDMORE-N.C.R.A.-GUTTON
 #8 Lunt
 Corner E/2 NW/4 NW/4 Sec. 25-26S-13W
 Pratt County, Kansas

15-151-10767-0000

Casing Record: Set 380' of 8-5/8" at 378' with 250 sacks. Cement
 circulated. 6-27-36.
 Set 4370' of 5-1/2" at 4347' with 75 sacks. 7-10-36.

Elevations: KB 1948
 DF 1948
 Gr 1943

<u>ELEVATIONS</u>	<u>DEPTH</u>
Soil and Clay	40
Sand	270
Shale and Shells	378
Red Rock and Shale	800
Shale and Shells	1525
Shale and Lime	1895
Lime	2080
Shale and Lime	2375
Shale and Lime	3130
Shale and Lime	3585
Shale and Lime	3875
Lime	3925
Lime	4165
Lime	4208
Shale and Lime	4245
Sand and Shale	4275
Sand and Lime	4348
Rotary Total Depth	4348
Cable Tool Total Depth	4351

6-20-66

RECEIVED
 STATE CORPORATION COMMISSION

LOGS

Lansing	JUN 20 1966	3738
Mississippi		4148
Viola	CONSERVATION DIVISION	4189
Simpson Shale	Pratt, Kansas	4229
Simpson Dolomite		4245
Arbuckle		4343

- DST #1 - 4151-4165 Shut in 20 min., open 1 hr., good blow, gas in 10 min., would not burn, not enough to gauge, shut in 20 min. Recovered 55' slightly gas cut mud. IBMP 1390, FBMP 431, IF 17, FF 17.
- DST #2 - 4168-4190 Shut in 20 min., open 1 hr., fair blow, shut in 20 min. Recovered 45' mud. IBMP 25, FBMP 45, IF 25, FF 40.
- DST #3 - 4195-4208 Shut in 20 min., open 1 hr., shut in 20 min., gas to surface in 7min. Recovered 165' oil and 180' muddy oil. IBMP 1428, FBMP 1345, IF 35, FF 145.
- DST #4 - 4209-4236 Shut in 20 min., open 1 hr., gas in 3 min., shut in 20 min. Recovered 375' oil and muddy oil, no water. IBMP 1438, FBMP 1235, IF 65, FF 165.
- DST #5 - 4241-4254 Shut in 20 min., open 1 hr., shut in 20 min., gas in 7 min. Recovered 270' muddy oil, trace of water. IBMP 755, FBMP 728, IF 135, FF 105.
- DST #6 - 4259-4269 Shut in 20 min., open 1 hr., shut in 20 min., Recovered 15' mud. IBMP 85, FBMP 85, IF 22, FF 27.

STATE OF KANSAS }
 COUNTY OF SLEDGWICK } ss

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above described, to the best of my knowledge and belief.

Subscribed and sworn to before me
 this 24th day of July, 1966.
 My Commission Expires: January 28, 1960

Robert P. Blle
 Leonard P. Blle