


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pratt County. Sec. 25 Twp. 26 Rge. 13 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines SW NW 1/4 W
Lease Owner Beardmore Drilling Company
Lease Name Lunt Well No. 4
Office Address Pratt, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 7-7-66 19
Plugging completed 7-16-66 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation Depth to top Bottom Total Depth of Well 4355 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	379'	None
				5-1/2"	4347'	3183'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to plug-back @ 4240', sanded hole to 4200' and dumped 5 sacks of cement @ 4200' with dump bailer. Pulled 5 1/2" casing, set rock bridge @ 340' and dumped 5 sacks of cement. Bailed hole to 325', and dumped 20 sacks of cement. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

8-2-66
STATE CORPORATION COMMISSION
AUG 2 1966
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of July, 1966

My commission expires May 20, 1968 Milton J. Volin Notary Public.

BEARDMORE-N.C.R.A.-SUTTON
#4 Lunt
SW NW NW, Section 25-26S-13W
Pratt County, Kansas

*Copies to
sent to
Pratt
Before plug check fluid
Level oil + water*

Casing Record:
Set 381' of 8 5/8" at 379' with 250 sacks. Cement circulated.
2-4-56.
Set 4347' of 5 1/2" at 4347' with 175 sacks. 2-22-56.

Elevations: KB 1945
DF 1942
Gr 1939

<u>FORMATIONS</u>	<u>DEPTH</u>
Cellar	5
Soil and Clay	35
Sand	250
Shale and Shells	350
Shale and Shells	1155
Lime and Shale	2025
Lime	2185
Lime and Shale	2415
Lime and Shale	3050
Lime	3230
Lime and Shale	3560
Lime and Shale	3803
Lime	3880
Lime	4015
Lime	4160
Lime	4210
Lime and Sand	4258
Sand	4275
Sand and Shale	4300
Lime	4355
Rotary Total Depth	4355

RECEIVED
STATE CORPORATION COMMISSION

<u>TOPS</u>		
Brown Lime		3709'
Lansing		3738
Viola Chert		4192
Simpson Shale		4233
Simpson Dolomite		4246
Arbuckle		4338

JUN 20 1966

CONSERVATION DIVISION
Wichita, Kansas

- DST #1 - 3765-3803' Open 1 hr. - good blow-shut in 15 mins. recovered 165' muddy water - slightly gas cut with few oil specks. IBHP 840 - FBHP 1100 - IF 70 - FF 110.
- DST #2 - 3923-3954' Open 1 hr-shut in 15 min.-good blow throughout. Recovered 60' slightly o.c.m. IBHP 100 - FBHP 90 - IF 50 - FF 50.
- DST #3 - 4196-4210' Shut in 15 min.-open 1 hr.-good blow-shut in 15 min. Recovered 5' slightly o & g.c.m. 60' o & g.c.m. IBHP 278 - FBHP 490 - IF 16 - FF 32.
- DST #4 - 4210-4233 Shut in 15 min.-gas in 4 min.-not enough to measure open 1 hr 5 min.-shut in 15 min. Recovered 330' oil, 120' muddy oil. IBHP 1415 - FBHP 968 - IF 48 - FF 165.
- DST #5 - 4247-4258 Shut in 15 min-open 1 hr.-gas in 17 min.-no measurement-shut in 15 min. Recovered 130' muddy oil.

IBHP 810 - FBHP 810 - IF 60 - FF 48.

STATE OF KANSAS }
COUNTY OF SEDGWICK) ss

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above described, to the best of my knowledge and belief.

Subscribed and sworn to before me
this 5th day of March, 1956.
Leonard P. Toll

Robert J. [Signature]