

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,885-00-00

LEASE NAME Hoeme

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 25 TWP. 26 RGE. 13 ~~W~~

COUNTY Pratt

Date Well Completed

Plugging Commenced 4-9-96

Plugging Completed 4-15-96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Rama Operating Company, Inc.

ADDRESS P.O. Box 159 Stafford, Ks. 67578

PHONE#(316) 234-5191 OPERATORS LICENSE NO. 3911

Character of Well Oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom 4319'

Show depth and thickness of all water, oil and gas formations. 4-22-96

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10 3/4"	332'	none
				5 1/2"	-4316'	2763'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each side. Plugged off bottom with sand to 3700' and 5 sacks cement. Shot well at 2909' and at 2763'. Pulled casing, pumped 400# hulls, 15 sacks gel, 60 sacks cement, 15 sacks gel, 100# hulls, release plug, pumped 155 sacks cement, 60/40 POZMIX 6% gel. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rama Operating Co., Inc. -Stafford, Ks. 67578

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P.O. Box 209 Chase, Kansas 67524.

SUBSCRIBED AND SWORN TO before me this 19th day of April, 19 96

James Herzberg
Notary Public

My Commission Expires:

