

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER None

LEASE NAME Tunt

WELL NUMBER 6 (SWD)

3960 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 25 TWP. 26 SRGE. 13 (X) or (W)

COUNTY Pratt

Date Well Completed 12/27/57

Plugging Commenced 9/12/90

Plugging Completed 9/27/90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Timberline Oil & Gas Corporation

ADDRESS 4447 S. Canyon Rd. Ste 1, Rapid City, SD

PHONE# (605) 341-3400 OPERATORS LICENSE NO. 9232

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 6, 1990 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? No; log sent with CP-1 Application

~~Rock~~ Formation Arbuckle Depth to Top 4390 Bottom 4565 T.D. 4565

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Saltwater	4390	4565	10 3/4"	380'	0
				7"	4390'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 0 feet to 800 feet each set. Pumped 88 Bbl 65/35 pos and 75 sx down 7" and circulate up 10 3/4" to surface. Pressure held at 300 psi. Run 1" PVC down 7"-10 3/4" annulus and circulate from 240' 90' sx 60/40 pos. Circulated clean cement to surface. Well has cement from 800' to surface inside 7", between the openhole and 7" casing and inside the 7"-
(If additional description is necessary, use BACK of this form.) 10 3/4" annulus.

Name of Plugging Contractor Allied Cementing Co. License No. ----

Address P.O. Box 31, Russell, KS 67665

STATE OF South Dakota COUNTY OF Pennington, ss.

Brant C. Grote (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Brant C. Grote*

(Address) 4447 South Canyon Rd. Ste 1
Rapid City, SD 57702

SUBSCRIBED AND SWORN TO before me this 2nd day of September 19 90

Trudy K. Steyer 10-5-90
Notary Public
My Commission Expires: 3/30/94

RECEIVED
STATE CORPORATION COMMISSION
Wichita, Kansas