


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Pratt County, Sec. 26 Twp. 26S Rge. (E) 13 (W)

Location as "NE/CNW/SW" or footage from lines C SW-NW
Lease Owner Amerada Petroleum Corporation
Lease Name Grace Hoener Well No. 2
Office Address Box 197, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-8-19- 19 60
Application for plugging filed 9-8-19- 19 60
Application for plugging approved 9-8-19- 19 60
Plugging commenced 9-8-20- 19 60
Plugging completed 9-8-20- 19 60
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19 -
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. Lackamp
Producing formation - Depth to top - Bottom - Total Depth of Well 4486 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	823'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Globe Cementing spotted cement plugs as follows:
Filled hole with heavy mud to 300'
spotted cement plug from 300' to 180' with 40 sacks cement.
Filled hole with heavy mud from 180' to 35'
spotted cement plug from 35' to top with 10 sacks cement.

9-26-60

RECEIVED
STATE CORPORATION COMMISSION

SEP 26 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barbour Drilling Company
Address 1579 E. 21 st - Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Barton, ss.
Ernest Higgins (employee of owner) ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Higgins
Ernest Higgins Foreman

(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of September, 19 60

Charles D. Anderson
Notary Public

My commission expires November 21, 1961

GRACE HOCNER #2

15-151-10926-0000

Center SW/4 NW/4 Section 26-268-13
Pratt County, Kansas
Amerada Petroleum Corporation

8-5/8" O. D. casing cemented at 823'

Drilling commenced 9-2-60
Drilling completed 9-20-60

FROM	TO	FORMATION	REMARKS
0'	150'	Sand & clay	
150	180	Sand	
180	230	Shale & shells	
230	245	Sand & shale	
245	770	Red bed	
770	1840	Shale & shells	8-5/8" O. D. casing cemented
1840	1915	Shale & streaks of anhydrite	with 400 sacks at 823'
1915	2055	Lime & shale	
2055	2180	Lime	
2180	2270	Shale & lime	
2270	2438	Lime & shale	
2438	2520	Shale	
2520	2650	Shale & lime streaks	
2650	2825	Shale & lime	
2825	2960	Shale	
2960	3060	Shale & lime	
3060	3170	Lime & shale	
3170	3270	Shale & lime	
3270	3340	Lime	
3340	3435	Lime & shale	
3435	3460	Shale & lime	
3460	3590	Lime	
3590	3675	Shale	
3675	3774	Sand & shale	
3774	4080	Lime	
4080	4120	Lime & shale	
4120	4165	Shale & lime	
4165	4249	Lime	
4249	4268	Miss. chert	
4268	4285	Chert	
4285	4300	Cherty lime	
4300	4317	Chert	
4317	4361	Cherty lime	
4361	4381	Lime & dolomite	
4381	4400	Chert, dolomite & sand	
4400	4406	Sand	
4406	4455	Sand & shale	
4455	4486	Sand & lime	Well plugged

10-3-60

RECEIVED
STATE CONSERVATION COMMISSION

OCT 3 1960

CONSERVATION DIVISION
Wichita, Kansas

T. D. 4486'

This is a true copy of the driller's log as shown on the drilling tickets.

BARBOUR DRILLING COMPANY

By: *A. M. Barbour*

Subscribed and sworn to before me on this 28th day of September, 1960.

Merry Jane Birt
Notary Public

My commission expires July 27, 1961