

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-01636-00-01  
Spot: SWNW Sec/Twnshp/Rge: 22-13S-14W  
3571 feet from S Section Line, 4514 feet from E Section Line  
Lease Name: ANSCHUTZ Well #: 4  
County: RUSSELL Total Vertical Depth: 640 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET (266 N. main ST. - suite 220)  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	640		175 sx

Well Type: SWD UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/21/2014 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: KCC Phone: (620) 727-3409

Proposed Plugging Method: Ordered 150 sx 60/40 pozmix 4% gel cement w/300 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/21/2014 11:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

01/20/2014- Well dug out and found 4 1/2" casing bent over. Surface pipe rusted and mostly gone. Set a piece of covert in and around old casing. Worked tubing in, drilled to 465' and bounced on iron.  
01/22/2014- Worked on drilling down with no headway. Ran tubing to 465' and pumped 75 sx cement. Circulated cement to surface. POOH. Pulled the piece of covert out of the cellar and pumped 20 sx cement in cellar. Cellar stayed full of cement. Site restored.  
GPS: 38.90992 -098.87037

Perfs:

Remarks: QUALITY WELL SERVICE TICKET # 6106 ANSCHUTZ FEE FUND PROJECT CONTROL # 20140043002

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Ray Dinkel*

(TECHNICIAN)

CM

JAN 11 2016

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

FEB 09 2016

CONSERVATION DIVISION  
WICHITA, KS