

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-20392-00-01
Spot: NWNWNW Sec/Twnshp/Rge: 13-14S-11W
(4968) ~~4957~~ feet from S Section Line, ~~5032~~ feet from E Section Line
Lease Name: ESCHBAUGH (4951) Well #: 2
County: RUSSELL Total Vertical Depth: 2946 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET (206 N. MAIN ST., SW 220)
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2651		100 sx
SURF	8.625	303		175 sx

Well Type: EOR UIC Docket No: E16313.1 Date/Time to Plug: 01/14/2014 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: KCC Phone: (620) 727-3409

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement.
Perforations: 1250', 570' and 250'.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/14/2014 3:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 2650' and pumped 100 sx cement. Pulled tubing to 1150' and pumped 85 sx cement. Cement circulated out backside. POOH. Hooked to casing and pumped 120 sx cement. Cement circulated out braden head. Shut in.
01/15/2014-Topped off well with 20 sx cement.

GPS: 38.84078 -098.50242

Remarks: QUALITY WELL SERVICE TICKET # 6105 ESCHBAUGH FEE FUND PROJECT CONTROL # 20140044001

Plugged through: TBG

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

JAN 25 2016

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

FEB 09 2016

CONSERVATION DIVISION
WICHITA, KS