

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-30054-00-00
Spot: SWSWSENE Sec/Twnshp/Rge: 29-34S-5E
2954 feet from S Section Line, 1008 feet from E Section Line
Lease Name: POTEET Well #: 1
County: COWLEY Total Vertical Depth: 2716 feet

Operator License No.: 34470
Op Name: VICTORY MINERALS LLC
Address: 11 N. SAINT JAMES PLACE
EASTBOROUGH, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5	2631		100 SXS CMT
PROD	5.5	2700		125 SX
SURF	8.625	160		130 SX
SURF	8	161		125 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/11/2016 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: LARRY ANSTINE Company: ANSTINE OIL CO Phone: (620) 441-8706

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/11/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2640', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL 2% CC & DISPLACED IN CASING. WAITED 2 HOURS, DID NOT TAG CEMENT. RIH W/TBG @ 2640', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL 2% CC & DISPLACED IN CASING. TAGGED CEMENT @ 2521'. RIH ON WIRELINE PERFORATED SQUEEZE HOLES @ 300'-301'. RIH W/TBG @ 320', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL, LAYED TUBING DOWN, SWEDGED INTO 5.5" CASING, MIXED & PUMPED 200 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. CEMENT TICKET #48415.

Perfs:

Top	Bot	Thru	Comments
2631	2716	CSG	

Remarks: COMPLIANCE / 10 YEAR RULE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)
KCC MEMBER

2-8-16

FEB 08 2016

RECEIVED

702-9-16
Form CP-2/3