

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-159-01956-00-00  
Spot: SWNENW Sec/Twnshp/Rge: 36-18S-8W  
4291 feet from S Section Line, 3548 feet from E Section Line  
Lease Name: CLARK WARNER Well #: 2  
County: RICE Total Vertical Depth: 3195 feet

Operator License No.: 9292  
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL  
Address: 211 S FRONT ST  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6	3182		250 SX
SURF	9.625	210		75 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/25/2016 12:00 PM  
Plug Co. License No.: 33369 Plug Co. Name: XTREME WELL SERVICE, INC.  
Proposal Rcvd. from: LEON HUXMAN Company: XTREME WELL SERVICE, INC. Phone: (785) 483-0567

Proposed Plugging Method: Run Tubing to bottom. Perforate and cement to bottom

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: PARTIAL  
Date/Time Plugging Completed: 01/25/2016 3:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND OFF LOWER PERFS TO 3130' AND CAP WITH 6 SX'S CEMENT. LET SET FOR AWHILE AND SANDED OFF UPPER PERFS TO 2750' AND CAPPED WITH 6 SX'S CEMENT. PERFORATE AT 1100', 750', AND 260'. RUN TUBING TO 1100' AND PUMP 50 SX'S CEMENT. LET SET FOR 1 HR, AND TAG AT 875'. PUMP 50 SX'S AT 750', PULL TUBING TO 260' AND CIRCUALTE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3181	3182	CSG	
2805	2807	CSG	

Remarks: LOG TECH OF KS. #8671. QUALITY CEMENT #1317. TA N.O.V.

Plugged through: TBG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

KCC WICHITA 2-8-16

FEB 08 2016

RECEIVED

Form CP-2/3

Mo 2-9-16

1x