

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-159-05838-00-00  
Spot: SWNESW Sec/Twnshp/Rge: 29-19S-9W  
1650 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: WALLACE Well #: 6  
County: RICE Total Vertical Depth: 3251 feet

Operator License No.: 30364  
Op Name: RESOURCE OPERATIONS, INC.  
Address: BOX 9487  
TULSA, OK 74157

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| PROD   | 7    | 3215       |             | 125 SX   |
| SURF   | 10   | 170        |             | 180 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/27/2016 11:30 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: LARRY OBERLE Company: RESOURCE OPERATIONS INC Phone: (620) 894-0203

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 01/27/2016 4:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PERFORATE AT 1200', 800', AND 250'. RUN TUBING TO 3200' AND PUMP 50 SX'S CEMENT WITH 100# COTTON HULLS. PULL TUBING TO 1200' AND PUMP 50 SX'S COMMON CEMENT WITH 2% CC. PULL TUBING UP TO 800' AND WAIT 1 HOUR. LOWER TUBING BACK DOWN AND TAG CEMENT AT 983'. PULL TUBING UP TO 800' AND PUMP 50 SX'S CEMENT, PULL TUBING TO 250' AND CIRCUALTE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3215 | 3251 |      | OH       |

Remarks: THIS WELL WAS SENT A TA - N.O.V. LETTER. LOG TECH OF KS. #8660. COPELAND #C-43599.

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)  
KCC WICHITA

FEB 03 2016 2-8-16  
RECEIVED  
Form CP-2/3  
200 2.9.16

✓