

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-21732-00-00
Spot: N2S2SWSE Sec/Twnshp/Rge: 20-19S-9W
546 feet from S Section Line, 1963 feet from E Section Line
Lease Name: VOLKLAND Well #: 9
County: RICE Total Vertical Depth: 3350 feet

Operator License No.: 30364
Op Name: RESOURCE OPERATIONS, INC.
Address: BOX 9487
TULSA, OK 74157

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3281		
CIBP		3303		
PROD	5.5	3349		175 SX
SURF	8.625	218		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/26/2016 10:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: LARRY OBERLE Company: RESOURCE OPERATIONS, INC. Phone: (620) 894-0203

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 01/26/2016 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PERFORATE AT 1200', 800', AND 270'. RUN TUBING TO 3214' AND PUMP 75 SX'S CEMENT. PULL TUBING TO 1200' AND PUMP 35 SX'S COMMON CEMENT WITH 3% CC. PULL TUBING UP TO 800' AND LET SET FOR 1.5 HR. LOWER TUBING BACK DOWN TAG CEMENT AT 852'. PULL TUBING UP TO 800' AND PUMP 35 SX'S, PULL TUBING UP TO 270' AND CIRCUALTE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3281	3284	CSG	
3258	3264	CSG	
3248	3252	CSG	
3245	3253	CSG	
3220	3232	CSG	
2988	2994	CSG	
2924	2926	CSG	

Remarks: A TA N.O.V. LETTER WAS SENT ON THIS WELL. LOG TECH OF KS. #8762. COPELAND #C43655.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)
KCC WICHITA

FEB 08 2016 2-8-16
RECEIVED

Form CP-2/3

720 2-9-16

1/26