

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21414-00-00
Spot: S2SEENENW Sec/Twnshp/Rge: 1-15S-30W
4030 feet from S Section Line, 2970 feet from E Section Line
Lease Name: ZIEGENBALG Well #: 1
County: GOVE Total Vertical Depth: 4352 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4205		
PROD	5.5	4350		110 SX
SURF	8.625	288		195 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/22/2016 10:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING Phone: (785) 421-2103

Proposed Plugging Method: Ordered 550 sx 60/40 pozmix 4% gel cement w/700 # hulls.
DV Tool at 2058' w/350 sx cement.
Packer stuck in hole at 4123'. Able to pump through.
CIBP set at 4205'
Perforations: 4162' - 4169' and 4328' - 4329'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/22/2016 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4097' and pumped 50 sx neat cement followed by 50 sx cement w/200 # hulls.
Pulled tubing to 3276' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 2291' and
pumped 100 sx cement. Pulled tubing to 1306' and pumped 80 sx cement. Good circulation of
cement. Pulled tubing out and topped off casing w/10 sx cement. Tied on to backside and
squeezed w/25 sx cement. Shut in pressure 100 psi.

GPS: 38.78296 -100.60651

Perfs:

Top	Bot	Thru	Comments
4328	4329		
4162	4169		

Remarks: HURRICANE SERVICES TICKET # 100617

Plugged through: TBG

District: 04

Signed _____


(TECHNICIAN) cm

Received
KANSAS CORPORATION COMMISSION

FEB 09 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

Handwritten: 2016-2-9-16