

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-21676-00-00
Spot: S2NWSENE Sec/Twnshp/Rge: 26-15S-14W
1850 feet from N Section Line, 990 feet from E Section Line
Lease Name: BENDER A Well #: 16
County: RUSSELL Total Vertical Depth: 3360 feet

Operator License No.: 30606

Op Name: MURFIN DRILLING CO., INC.

Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3352		250 SX
SURF	8.625	346		250 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/13/2016 7:30 AM

Plug Co. License No.: 34059

Plug Co. Name: HURRICANE SERVICES, INC.

Proposal Rcvd. from: STAN FROETSCHNER

Company: MURFIN DRILLING CO., INC.

Phone: (785) 483-1197

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement, 500 # hulls and 15 sx gel.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 01/13/2016 12:30 PM

KCC Agent: RAY DINKEL

Actual Plugging Report:

Holes in casing found at 1400' - 1460' and 320'. Well was two staged. Ran tubing to 3320' and pumped 15 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1510' and pumped 175 sx cement w/200 # hulls. Started to circulate cement and pumped an additional 20 sx cement. POOH. Hooked to casing and pumped 10 sx cement at 200 psi to shut in. Hooked to Braden Head and pumped 30 sx cement at 200 - 250 psi to shut in.

GPS: 38.72082 -098.84141

Perfs:

Top	Bot	Thru	Comments
3352	3354		

Remarks: HURRICANE CEMENTING SERVICE TICKET # 100662

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

CM

JAN 19 2016

FEB 09 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

no 2-9-16