

TO: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-191-22631-01-00
 Spot: N2N2NENE Sec/Twnshp/Rge: 3-34S-4W
180 feet from N Section Line, 660 feet from E Section Line
 Lease Name: SCHMIDT 3-34-4 Well #: 1H
 County: SUMNER Total Vertical Depth: 8670 feet

Operator License No.: 32334
 Op Name: CHESAPEAKE OPERATING, LLC
 Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	120		168 sx cement
	II 4.5	8670		400 sx cement
PROD	7	4964		400 SX
SURF	9.625	500		270 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/05/2014 12:00 AM
 Plug Co. License No.: 8733 Plug Co. Name: DUNKIN, JERRY, INC.
 Proposal Rcvd. from: JERRY DUNKIN Company: JERRY DUNKIN Phone: (580) 824-7251

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
 Date/Time Plugging Completed: 03/17/2014 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET 7" CIBP AT 3400' AND 2 SKS OF CEMENT. RAN TUBING TO CIBP AND LOADED HOLE WITH PLUG MUD. PERFORATED 7" CASING AT 830' AND PUMPED 75 SKS OF CEMENT. TAG CEMENT AT 785'. PERFED 7" CASING AT 550' AND CIRUCALTED 287 SKS OF CEMENT TO 0'. CLASS A CEMENT.

Perfs:


Top	Bot	Thru	Comments
8546	8547	CSG	
8460	8461		
8364	8365		
8282			8283
8198	8199		
8091	8092		
8000	8001		
7896	7897		
7786	7787		
7690	7691		
7572	7573		
7480	7481		
7370	7371		
7272	7273		
7056	7057		
6960	6961		
6858	6859		
6760	6761		
6666	8547		
1765	7166		

TVD 8670
 TMD (Kickoff) 43.70
 billed/Invoiced 2.9.16 70

Remarks: JERRY DUNKIN CLASS A

Plugged through: TBG
TMD 4370

District: 02

Signed 

KCC MONTA

FEB 08 2016

RECEIVED

2.9.16
 Form CP-2/3