

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-24180-00-00
Spot: NWSENESW Sec/Twnshp/Rge: 17-9S-17W
1700 feet from S Section Line, 2300 feet from W Section Line
Lease Name: PRESTON Well #: 1
County: ROOKS Total Vertical Depth: 3660 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3628		150 SX
SURF	8.625	261		155 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/18/2016 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1928

Proposed Plugging Method: Port Collar set at 1457' w/140 sx cement.
LKC Perforations: 3332' - 3478'.
Low Fluid Level; Top Down Plug Job.
Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 01/18/2016 10:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 325 sx cement w/500 # hulls down 5 1/2" casing. Maximum pressure 700 psi.
Shut in pressure 500 psi. Hooked to backside with instant pressure of 300 psi.

Perfs:


Top	Bot	Thru	Comments
3474	3478		
3383	3385		
3334	3338		
3332	3335		

Remarks: ALLIED TICKET # 055407

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

CR

FEB 09 2016

CONSERVATION DIVISION

Form CP-2/3

2-9-16