

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-20945-00-00
Spot: N2S2SE Sec/Twnshp/Rge: 21-16S-10W
990 feet from S Section Line, 1320 feet from E Section Line
Lease Name: STOLTENBERG C Well #: 1
County: ELLSWORTH Total Vertical Depth: 3350 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3349		150 SX
SURF	8.625	389		210 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/19/2016 12:00 PM
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.
Proposal Rcvd. from: TODD L. DINKEL Company: PATRIOT WELL SERVICE, INC. Phone: (785) 483-1307

Proposed Plugging Method: AS PER KCC RULES & REGS. KNOWN CASING LEAK @ 510'-637', LISTED ON CP-1.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 01/20/2016 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 2950' AND CAP WITH 5 SX'S CEMENT. PERFORATE AT 1350', 1050', AND 440'. RUN TUBING TO 1350' AND PUMP 5 SX'S GEL FOLLOWED BY 35 SX'S COMMON CEMENT. PULL TUBING UP TO 850' AND LET SET FOR 2 HOURS. ATTEMPTED TO TAG CEMENT, APPEARED THAT CEMENT WAS NOT AT 1350'. PUMPED 50 MORE SX'S AT 1350', PULLED TUBING OUT OF HOLE AND QUIT FOR THE DAY. CAME BACK ON 1-20-16 AND TAGGED CEMENT AT 1140' WITH TUBING. PULLED TUBING TO 1050' AND PUMPED 35 SX'S, PULLED TUBING TO 550' AND CIRCULATED CEMENT TO SURFACE. PULLED TUBING OUT AND TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
3311	3314	CSG	
3254	3257	CSG	
3182	3184	CSG	
3028	3032	CSG	

Remarks: THIS WELL HAD A TA N.O.V. LETTER. OPERATOR TESTED 3-KC ZONES, BUT DID NOT PRODUCE. GEMINI WIRELINE #2283. GLOBAL CEMENTING TICKET 2577 & 2578.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

KCC WICHITA

FEB 03 2016

RECEIVED

no 2-9-16
Form CP-2/3

2-8-16