

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-21492-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 8-19S-6W
3630 feet from S Section Line, 2310 feet from E Section Line
Lease Name: LIGHTHILL Well #: 6
County: RICE Total Vertical Depth: 3414 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3100		
PROD	5.5	3414		125 SX
SURF	8.625	259		180 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/21/2016 3:45 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 01/21/2016 3:45 PM KCC Agent: VERGIL CLOTHIER

Actual Plugging Report:

MIRU, CK'D PB DEPTH. SET CIBP AT 3080' AND CAPPED WITH 2 SX'S CEMENT. PERFORATE AT 900', 550', AND 310'. RUN TUBING TO 900' AND PUMP 35 SX'S CEMENT. PULL TUBING UP TO 550'. LET SET FOR 1 HOUR, TAG CEMENT WITH SWAB BAR AT 730'. PUMPED 35 SX'S AT 550', PULL TUBING TO 310' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3157	3176	CSG	

Remarks: LOG TECH OF KS #8659. COPELAND TICKET #C-43597.

Plugged through: TBG

District: 02

Signed

Vergil Clothier
(TECHNICIAN)

KCC WICHITA

FEB 08 2016

RECEIVED

Form CP-2/3

NO
2-9-16

✓