

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-24618-00-01
Spot: SENENW Sec/Twnshp/Rge: 31-11S-20W
4125 feet from S Section Line, 3070 feet from E Section Line
Lease Name: HUCKA Well #: 5-D
County: ELLIS Total Vertical Depth: 3936 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 345 RIVERVIEW ST., STE 540
WICHITA, KS 67203

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3931		275 sx
SURF	8.625	254		225 sx

Well Type: EOR UIC Docket No: E30680.1 Date/Time to Plug: 01/12/2016 9:30 AM
Plug Co. License No.: 34272 Plug Co. Name: OUTLAW WELL SERVICE LLC
Proposal Rcvd. from: RANDY WEIGEL Company: EMPIRE ENERGY E & P Phone: (785) 737-3736

Proposed Plugging Method: Emergency Plug with rig over hole.
Ordered 480 sx 60/40 pozmix 4% gel cement w/1000 # hulls.
PBTB: 3800'
DV Tool: 1660' w/450 sx cement
Perforations: 3666' - 3671', 3722' - 3725'. Bad casing leaks.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/12/2016 12:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Out Law Well Service ran in hole with tubing to 3615'. Quality rigged to tubing and pumped 150 sx cement w/400 # hulls mixed in. Pulled tubing to 2500'. Quality rigged to tubing and pumped 150 sx cement w/300 # hulls. Pulled tubing to 1300'. Quality rigged to tubing and pumped 140 sx cement w/300 # hulls to circulate cement to pit area. Pulled tubing. Rigged to 5 1/2" casing and pumped 20 sx cement w/400 # hulls. Shut in pressure 400 psi. Rigged to 8 5/8" surface pipe and pumped 10 sx cement to pressure with 200 psi. Shut in pressure 200 psi.

GPS: 39.05599 -099.58571

Perfs:

Remarks: QUALITY CEMENTING CO TICKET # 1314

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

JAN 13 2016

Received
KANSAS CORPORATION COMMISSION

FEB 09 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

no
2-9-16
cc-llc