

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-00163-00-01
Spot: NENW Sec/Twnshp/Rge: 36-29S-7W
4620 feet from S Section Line, 3300 feet from E Section Line
Lease Name: BARNEY A Well #: 1
County: KINGMAN Total Vertical Depth: 5237 feet

Operator License No.: 8740
Op Name: BRAMWELL PETROLEUM, INC.
Address: 12826 SW 77 AVE
ZENDA, KS 67159

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4687		150 SX
SURF	8.625	175		125 SX

Well Type: SWD UIC Docket No: D08385.0 Date/Time to Plug: 01/19/2016 12:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: DOUG BRAMWELL Company: BRAMWELL PETROLEUM INC Phone: (620) 532-6019

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/29/2016 10:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

CASING LEAK AND TUBING PART AT 2912'. UNABLE TO MILL OUT AND REPAIR. TOF AT 2947'. RAN 2 INCH TUBING TO 2914' AND SPOTTED 30 SKS OF CEMENT. WAITED 1.5 HRS AND TAGGED CEMENT AT 2800'. PERFOATED CASING AT 1200' AND SPOTTED 30 SKS OF CEMENT THRU TUBING AT 1130'. TAGGED CEMENT AT 1140'. PERFORATED CASING AT 700', RAN TUEING TO 645' AND SPOTTED 30 SKS OF CEMENT. TAGGED CEMENT AT 450'. PERFORATED CASING AT 250', TIED ONTO CASING AND CIRCUALTED CEMENT UP ANNULAS WITH 110 SKS OF CEMENT.

Perfs:


Top	Bot	Thru	Comments
4687	5237	OH	

Remarks: HURRICANE SERVICES INC. CLASS A CEMENT 3% CACL.

Plugged through: TBG

District: 02

Signed _____



TECHNICIAN
KCC WICHITA

FEB 03 2016

RECEIVED

2-3-16

Form CP-2/3

no
2.9.16
cc to KIC