

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-20926-00-00
Spot: NWNENW Sec/Twnshp/Rge: 1-11S-31W
4950 feet from S Section Line, 3630 feet from E Section Line
Lease Name: BAALMAN Well #: 1
County: GOVE Total Vertical Depth: 4650 feet

Operator License No.: 30104
Op Name: CAMBRON, PAUL L.
Address: 118 N PENN PO BOX 384
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4643		175 SX
SURF	8.625	217		140 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/19/2016 11:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: HAL HOSS Company: CAMBRON, PAUL L. Phone: (785) 798-5051

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/700 # hulls.
Port Collar at 2549' w/475 sx cement.
Perforations: 4161' - 4163', 4192' - 4195', 4200' - 4205', 4209' - 4211', 4214' - 4218', 4248' - 4250', 4274' - 4276', 4458' - 4464', 4482' - 4484' and 4593' - 4598'.

Plugging Proposal Received By: DARREL DIPMAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/20/2016 11:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4168' and pumped 100 sx cement 300 # hulls. Pulled tubing to 3100' and pumped 200 sx cement w/400 # hulls. No circulation of cement. Pulled tubing out and shut down for the day.
01/19/2016- Tagged cement at 550'. Ran tubing to 545 and pumped 70 sx cement. Good circulation of cement. Pulled tubing out and topped off casing w/5 sx cement. Tied on to backside and squeezed w/5 sx cement. Shut in pressure 150 psi.
GPS: 39.13247 -100.71358


Perfs:

Top	Bot	Thru	Comments
4593	4598		
4203	4205		
4161	4163		

Remarks: SWIFT CEMENT TICKET # 28760

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

FEB 09 2016

CONSERVATION DIVISION
WICHITA, KS

no 2.9.16