

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-22014-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 3-32S-7E
2310 feet from N Section Line, 2310 feet from E Section Line
Lease Name: ANKROM Well #: 7
County: COWLEY Total Vertical Depth: 2516 feet

Operator License No.: 34798 •
Op Name: VIKING PRODUCTION LLC
Address: 1432 NIGHTHAWK RD
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2516		200 sx
SURF	8.625	201		75 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/18/2015 9:00 AM
Plug Co. License No.: 34798 Plug Co. Name: VIKING PRODUCTION LLC
Proposal Rcvd. from: BERT CARLSON Company: VIKING PRODUCTION, LLC Phone: (620) 625-2067

Proposed Plugging Method: AS PER KCC RULES & REGULATIONS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 12/01/2015 10:30 AM KCC Agent: DAN FOX

Actual Plugging Report:

RAN 2 3/8" TUBING TO BOTTOM AND SPOT 30 SX OF CEMENT FOR BOTTOM PLUG. RAN BACK IN AND TAGGED TOP OF CEMENT AT 1,218'. PERFORATED AT 350' AND CIRCUALTED CEMENT TO SURFACE, TOPPED OFF WELL AND CUT SURFACE PIPE OFF BELOW SURFACE. 125 SX TOTAL. PLUG JOB COMPLETE. CONSOLIDATED OIL WELL SERVICES, LLC. CEMENT TICKET #51090.

Perfs:

Top	Bot	Thru	Comments
2160	2170		TBG

Remarks: WELL WAS PLUGGED AS A RESULT OF PENALTY ORDER AND COMPLIANCE AGREEMENT.

Plugged through: TBG

District: 02

Signed 
(TECHNICIAN)

KCC WICHITA
FEB 08 2016
RECEIVED

Form CP-2/3
no 2-9-16