

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

August 20, 1964

RECEIVED  
 STATE CORPORATION COMMISSION

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

AUG 27 1964

8-27-64

CONSERVATION DIVISION  
 Wichita, Kansas

Dear Sir:

Mr. Russell Hoberecht of Ace Pipe Pulling Co. has this

date requested permission to plug the following described well:

Mr. Hoberecht guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Company

Complete Address: P.O. Box 649, Mc Cook, Nebraska

Lease Name: G. F. Milburn Well No. 1

Location: C N $\frac{1}{2}$  NW SE Sec. 24 Twp. 24 Rge. 8  (W) X

County Reno Total Depth 3541' Oil Well  X

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Hoberecht was instructed to plug the well as follows:

Fill hole with sand to 3515' and cement with 5 sacks.

Fill hole with mud to 280'. Set rock bridge from 280'

to 270' and cement hole with 20 sacks. Fill hole with

mud to 40'. Set rock bridge from 40' to 30' and cap

hole with 10 sacks cement.

Very truly yours,

  
 Conservation Division Agent