



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 116-4

LOCATION NW-NW-NE

SEC. 23 TWP. 24 RGE. 11-w

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease W. C. Volker

Operator Standard Oil Co Address Box #7 - Ellinwood - Kans.

Field _____ County Stafford

Total Depth 3830 Feet.

(Describe briefly the manner in which the well was plugged)

Sucker Pipe 10 3/4 - 238 ft - Circulated with cement.
7" casing set at 3800 ft - Plugged back down bottom to 3800 ft
with shot - Dumped 3 sacks of cement at 3800 ft - Shot off & pulled
the 7" casing - Filled with mud to 238 ft - Set Rock Bridge &
20 sacks of cement at 238 ft - Mud to 30 ft - Bridge & 10 sacks
of cement at the surface -
Pipe Pulling, Inc. - Plugging Contractors -

RECEIVED
C. W. Stough - 12-1-49

District Conservation Agent

Date 11-27-49 3N

STATE CORPORATION COMMISSION
KANSAS

PLUGGING
FILE SEC 23 TWP 24 RGE 11W
BOOK PAGE 116 LINE 4