

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 47-14LOCATION SE-NE-2201SEC. 23 TWP. 24 RGE. 11-WDry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 27 Lease W. H. Ferris - "B"Operator Standard Oil & Gas Address Box 7 Ellinwood, Kans.Field _____ County StaffordTotal Depth 3811 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 255 ft. Circulated with cement
7 casing set at 3789 ft. Cemented with 100 sacks cement.
Plugged back to 3780 ft with chat - Dumped 6 sacks of
cement at 3780 ft. Shot off & pulled the 7 casing
 Mud to 255 ft. Set Block Bridge & 10 sacks of
cement at 255 ft. Mud to 30 ft. Plug &
10 sacks of cement at the surface.
Pipe Pulling, Inc. Plugging - Contracted

DEC 26 1950

12-26-50 CONSERVATION DIVISION
Wichita, Kansas

C. W. Stough
District Conservation Agent

Date 12-22-50

PLUGGING
FILE SEC 23 T 24 R 11W
BOOK PAGE 47 LINE 14