

*B*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 106-3

LOCATION NE-NE-NE

SEC. 23 TWP. 24 RGE. 11-W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 4 Lease W. C. Volker

Operator Standard Oil & Gas Co Address Box #7 - Ellinwood - Kans.

Field \_\_\_\_\_ County Stafford

Total Depth 3808 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 13" - 248ft - Circulated with cement.  
7" casing set at 3800ft - Filled back from bottom  
to 3800ft with chat - Dumped 5 sacks of cement  
at 3800ft - Shot off & pulled free 7" casing - Filled  
with mud to 248ft - Rock Bridge & 20 sacks of cement  
at 248ft - Mud to 15ft - Bridge & 10 sacks of cement  
at the surface - Frank Correll - Plugging - Contractor

RECEIVED C. M. Stough  
District Conservation Agent

**PLUGGING**  
FILE SEC 23 T 24 R 11W  
ROCK 106 LINE 3 ST

Conservation Div. Date 8-19-49

AUG 22 1949

STATE CORPORATION COMMISSION  
KANSAS  
8-22-49