

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pratt

County. Sec. 3 Twp. 29 Rge. 15 (E) (W)

Location as "NE/CNW%SW%" or footage from lines SW SW NE

Lease Owner Rupp Ferguson Oil Company

Lease Name BROWN Well No. 1

Office Address 518 Petroleum Building, Wichita, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 1, 1954

Application for plugging filed verbally June 1, 1954

Application for plugging approved verbally June 1, 1954

Plugging commenced June 1, 1954

Plugging completed June 1, 1954

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 4836 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	318"	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 300'
Set first plug at 300' with 20 sacks cement & 1 1/2 gal. hulls.
Filled hole with mud to 35'
Set second plug at 35' with 10 sacks cement & 1 1/2 gal. hulls.

Name of Plugging Contractor Musgrove Petroleum Corporation
Address 518 Petroleum Building, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick
I, Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
518 Petroleum Building, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of June, 1954

My commission expires September 24, 1956.

Notary Public

PLUGGING
FILE SEC 3 T 29 R 15W
BOOK PAGE 39 LINE 16

RECEIVED
STATE CORPORATION COMMISSION
JUN 2 - 1954 6-9-54
CONSERVATION DIVISION
Wichita, Kansas

CONTRACTOR'S WELL LOG

COMPANY: Rupp Ferguson Oil Company
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: Brown #1
 LOCATION: SW SW NE, Section 3-29-15
 Pratt County, Kansas.
 COMMENCED: May 14, 1954
 COMPLETED: June 1, 1954

0	5	Cellar
5	30	Sandy clay
30	132	Sand & river gravel
132	220	Sandy blue shale
220	499	Red bed
499	530	Red bed sand
530	878	Red bed & shale
878	892	Anhydrite
892	1030	Shale
1030	2020	Shale & shells
2020	4060	Shale & lime
4060	4411	Lime
4411	4456	Lime & shale
4456	4525	Lime
4525	4533	Mississippi lime
4533	4674	Lime & chert
4674	4691	Simpson shale
4691	4713	Shale
4713	4836	Lime
	4836'	Rotary Total Depth

Set 8-5/8" surface pipe at 318' with 225 sacks of cement and 2 calcium chloride.

Dry and Abandoned

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the BROWN #1, SW SW NE, Section 3-29-15, Pratt County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By *Gordon L. Koelling*
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 8th day of June, 1954.

Thomas P. Stump
 Notary Public

My commission expires September 24, 1956.

PLUGGING
 FILE NO. 3129 (SW)
 PAGE 37 LINE 16

RECEIVED 6-9-54
 CORPORATION COMMISSION
 JUN 9 - 1954
 CONSERVATION DIVISION
 Wichita, Kansas