

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

00-05

API NUMBER 15-151-21,519  
 LEASE NAME Maxedon Trust  
 WELL NUMBER #1

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

         Ft. from S Section Line  
         Ft. from E Section Line  
 SW/4 SW/4 SE/4  
 SEC. 4 TWP. 29S RGE. 15W(E) or (W)

LEASE OPERATOR Raymond Oil Co., Inc.  
 ADDRESS P.O. Box 48788  
Wichita, Kansas 67201  
 PHONE# (316) 267-4214 OPERATORS LICENSE NO. 5046

COUNTY Pratt  
 Date Well Completed           
 Plugging Commenced 8-9-88  
 Plugging Completed 8-18-88

Character of Well Oil  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes  
 Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filled?          If not, is well log attached?           
 Producing Formation          Depth to Top          Bottom          T.D. 4850'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	373'	none
				5-1/2"	4848'	3056'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.  
Plugged off bottom with sand to 4410' and 5 sacks cement. Shot pipe @3340', 3056', pulled a total of 82 joints of 5-1/2" casing. Plugged surface with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, 100 sacks cement, 60/40 pos., 6% gel. Plugging Complete.  
 (if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050  
 Address P.O. Box 347 Chase, Kansas 67524  
 STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso  
 Box 347  
 (Address) Chase, Kansas 67524

8-23-88  
 DESCRIBED AND SWORN TO before me this 19th day of August, 19 88

Jane Hoover  
 Notary Public

RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 23 1988  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

Commission Expires:  
