

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Pratt

County. Sec. 8 Twp. 29S Rge. (X) 15 (W)

Location as "NE/CNW%SW%" or footage from lines C NW SE

Lease Owner: National Drilling Company, Inc.

Lease Name Bryant Well No. 1

Office Address 535 Petroleum Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9/15/60 19

Application for plugging filed 9/15/60 19

Application for plugging approved 9/15/60 19

Plugging commenced 8AM, 9/15/60 19

Plugging completed 10AM, 9/15/60 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bice Lackamp Jr., Stafford, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4700 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	335'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from Total Depth, 4700', to 220'.

Set 1st plug @ 220' with 20 sacks cement.

Filled hole with mud from top of 1st plug to 35'.

Set 2nd plug @ 35' with 10 sacks cement.

Filled with mud to surface.

RECEIVED
STATE CORPORATION COMMISSION

SEP 21 1960 9-21-60

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor National Drilling Company, Inc

Address 535 Petroleum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Howard A. Stoskopf (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Howard A. Stoskopf

535 Petroleum Building, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 19 day of September, 1960

W. Irene Harcourt Notary Public.

My commission expires August 5, 1961



DRILLERS LOG

BRYANT No. 1

CASING RECORD: COMPANY: NATIONAL DRILLING CO., INC.
 8 5/8" @ 335'
 w/250 sx. Cement Contractor: Same

DESCRIPTION: C NW SE COMMENCED: 9/1/60
 8-29S-15W COMPLETED: 9/15/60
 Pratt County, Kansas

TOTAL DEPTH: 4700 ELEVATION: 2031 KB.

<u>FORMATION:</u>	<u>FROM</u>	<u>TO</u>
Surface Clay and Sand	0	95
Red Bed	95	335
KANSAS Shale and Shells	335	2075
Lime	2075	2490
Shale and Lime	2490	2575
Lime	2575	2860
Shale and Lime	2860	3210
Shale	3210	3305
Shale and Shells	3305	3370
Lime and Shale	3370	3620
Lime and Chalk	3620	3755
Lime	3755	4480
Lime and Shale	4480	4510
Conglomerate	4510	4555
Lime	4555	4596
Lime and Chert	4596	4633
Lime	4633	4690
Lime and Chert	4690	4700

9-21-60
 RECEIVED
 STATE CORPORATION COMMISSION
 SEP 21 1960
 CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

NATIONAL DRILLING COMPANY, INC.

Howard A. Stoskopf
 Howard A. Stoskopf

Subscribed and sworn to before me this 19 day of September 1960.

M. Irene Harcourt
 Notary Public

My Commission Expires August 5, 1961