


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Re
WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Pratt County, Sec. 35 Twp. 29 Rge. 14 (E) W. (W)
Location as "NE/CNW/SW" or footage from lines 990' N. & 330' W. of SE Cor.
Lease Owner Cities Service Oil Company
Lease Name Shriver "B" Well No. 3
Office Address Box 144, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed March 17 19 53
Application for plugging filed September 17 19 60
Application for plugging approved September 17 19 60
Plugging commenced September 17 19 60
Plugging completed September 22 19 60
Reason for abandonment of well or producing formation Depleted formation.

If a producing well is abandoned, date of last production June 15 19 60
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hempel
Producing formation Simpson Depth to top 4431 Bottom 4446 Total Depth of Well 4515 Feet
Show depth and thickness of all water, oil and gas formations. P. B. Total Depth 4480'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	412'	None
				5-1/2"	4512'	2820'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4480-4400', sand.
4400-4368', 4 sacks cement.
4368- 300', mud.
300- 290', rock bridge.
290- 230', 20 sacks cement.
230- 35', mud.
35- 30', rock bridge.
30' to base of cellar, 10sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1960
10-14-60
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C. E. Shull Casing Pulling Co.
Address Box 558, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
John D. Forsyth (employee of owner) ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John D. Forsyth
Box 144, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of October 19 60

My commission expires March 12, 1963.

W. D. Smith
Notary Public.



COPY


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CITIES SERVICE OIL COMPANY
Farm- Schriver "B" No. 3

SEC. 35 T. 29 R. 11W
NE SE SE
990' N & 330' W of SE corner

Total Depth. 4515 SLM
Comm. 1-14-53 Comp. 1-31-53
Shot or Treated.
Contractor. Barbour Drilling Co.
Issued. 4-18-53

County Pratt
KANSAS



Elevation. 1967 C.T. D.F.

Production. Phy. pot. 43 bbls &
no wtr

CASING:

8 5/8" 412' cem w/225 sx
5 1/2" 4512' cem w/200 sx

Figures indicate Bottom of Formations.

surface clay, shale	70
sand	185
red bed, shale	305
redbed, shale, shells	1020
shale, shells	1975
lime, shale	2185
lime	2265
lime, shale	2635
lime	2695
lime, shale	2870
shale	3150
lime, shale	3360
lime	3375
shale, lime	3605
lime	3755
lime broken	3870
lime	3973
lime, shale	4025
lime	4420
lime cherty	4442
sand	4445
lime, shale	4515
lime	4520

4520 RTD = 4515 SLM
Total Depth

Tops: Corr.	
Brown LS.	3950
Lansing	3964
Viola	4417
Simpson shale	4424
Simpson sand	4432
Arbuckle	4510
Penetration	5'

All Date Corrected to Cable
Tool floor: Elevation 1967.

Well full oil & flowing in 3
hrs. 15 mins. from Arbuckle.