

PRYOR AND LOCKHART, INC.
Bergner No. 1.

SEC. 35 T. 29 R. 14W.
NEc NE

Total Depth. 4774 P.B. 4545
Comm. 7-25-41 Comp. 9-18-41
Shot or Treated.
Contractor. Pryor and Lockhart, Inc.
Issued. 9-27-41

County Pratt.



CASING.

13" 310' cemented.
7" 4577' cemented.

Elevation.

Production. DRY

Figures Indicate Bottom of Formations.

cellar	12	broken limo	3170	limo	4583
clay	18	limo	3258	chort	4585 $\frac{1}{2}$
sand	165	limo broken	3262	sand	4587
shale and sand	205	limo soft	3269	limo	4596
red rock	370	limo broken	3286	sdv shale	4601
red rock and sand	630	limo	3298	sand	4612
shale blue & shells	680	limo soft	3303	shalo	4618
red rock	755	limo	3340	shalo & sand	4623
shells and shale	778	broken limo	3355	sand	4625
lime	798	limo	3368	shale	4670
shale and shells	1000	shalo	3376	limo broken	4675
red rock and blue shale	1090	limo	3415	limo	4707
shale blue	1130	limo soft	3430	limo & chort	4711
shale and salt	1170	broken limo	3436	limo	4734
shale	1270	limo	3473	chort and limo	4774
shale grey	1350	limo soft	3485	Total Depth.	
red rock	1375	limo	3495	Plugged back to 4615 8-30-41	
shale blue	1400	limo broken	3550	Plugged back to 4545 9-15-41	
shale and shells	1715	limo	3572	55 shots Lanc Wells 4124-35	
broken lime & shale	1810	broken limo	3596	and from 4063-74 9-18-41	
lime	1840	limo	3625	40 qts 4578-4605	
shale	1965	limo soft	3635	TOPS - Anhydrito 778	
lime	1993	shalo	3670	Lansing K.C. 4014	
shale	2008	limo	3680	Viola 4514	
lime	2010	limo soft	3717	Simpson 4580	
lime&shale brakos	2114	lime hard	3724	Arbucklo 4668	
broken lime and shale		lime & shale		small show oil 4129-35	
brakos	2200	brakos	3774	show 4582-4605	
shale and lime	2245	shalo	3785		
lime	2280	broken limo and			
shale	2290	shalo	3826		
lime and broken shale	2330	broken limo	3883		
sand	2334	limo and shale	3933		
lime	2350	shalo	3952		
shale and shells	2420	sand and shale	3980		
broken lime and shale	2435	shale & shells	4014		
lime	2495	limo	4065		
broken lime	2518	limo soft	4075		
shale and lime	2560	limo	4129		
lime	2625	broken limo	4132		
broken lime and shale	2698	limo	4165		
lime	2708	broken limo	4175		
shale	2722	lime soft	4187		
lime	2730	limo	4292		
shalo	2735	limo soft	4300		
lime	2754	limo hard	4306		
shale	2760	limo	4368		
lime	2782	lime broken	4380		
lime and shale	2835	limo	4389		
shale	2890	chert and limo	4412		
lime and shale	2972	shalo	4430		
shale and limo	3020	lime and shale			
lime	3030	brakos	4464		
shale and lime	3045	cherty limo	4484		
shalo	3075	lime soft	4487		
lime Porous	3085	shalo	4499		
shale	3090	lime soft	4506		
shalo and shells	3138	chert	4511		
shalo sticky	3148	limo	4541		
shalo	3162	broken limo	4546		

PLUGGING
FILE - EC 35: 29 R 14W
BOOK PAGE 11 LINE 12

