

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.--82-3-117

API NUMBER 15,151-21,429-00-00

LEASE NAME Bergner

WELL NUMBER #1

4290 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 35 TWP. 29 RGE. 14 (E) or (W)

COUNTY Pratt

Date Well Completed _____

Plugging Commenced 7-22-87

Plugging Completed 7-31-87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR State Corporation Commission

ADDRESS 202 W. First St. Wichita, Kansas 67202

PHONE# (316)225-6760 OPERATORS LICENSE NO. N/A

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? One (1)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4669'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	251'	None
				4-1/2"	4669'	2,920.45'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 4450' and 4 sacks cement. Shot casing at 3700' and 2300'. Pulled 71 joints of 4-1/2" casing. B.J. Titan squeezed well with 300 lbs. hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100 lbs. hulls, released plug and pumped 100 sacks 50/40 pozmix cement with 6% gel. Maximum pressure was 550 psi and shutin 150 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.


James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
 (Address) James W. Rockhold
Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 4th day of August, 19 87

Iona M. Leatherman
 Notary Public

My Commission Expires: _____



Recd
 8-4-87