

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-015-20414-00-00

API NUMBER N/A

LEASE NAME GRAY

WELL NUMBER 4

330' Ft. from North Section Line

4950' Ft. from E Section Line

SEC. TWP. RGE. (E) or (W)

COUNTY Butler

Date Well Completed

Plugging Commenced 8/29/95

Plugging Completed 8/31/95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR LEE PHILLIPS OIL CO.

ADDRESS 151 Whittier, St. 1400, Wichita, Ks 67207

PHONE# (316) 681 4470 OPERATORS LICENSE NO. 5215

Character of Well

(Oil Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/31/95 (date)

by Jerry Clark (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? no

Producing Formation Depth to Top Bottom T.D. 2789'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	211'	0
				5 1/2	2785'	1058'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pull rods and tubing. Strung tools into 2620'. Plug back with sand to 2550'. Mix & dump 6 sacks cement @ 2550'. Dug cellar. Ripped 5 1/2" csg @ 1160' and 1058'. Pulled 33 jts 5 1/2" csg. 1058'. Put rock bridge 300' to 280'. Bail hole dry. to 280'. Had 4 1/2 yds slurry mix cement put from 280' to surface.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor DALE WILSON d/b/a W.W. DRILLING CO License No. 6012

Address 3603 NE Fourth St., El Dorado, Ks. 67042 8666 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lee Phillips Oil Co. **SEP 13 1995**

STATE OF Kansas COUNTY OF Butler, ss.

Dale Wilson, plugging contractor (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dale Wilson

(Address) 3603 NE 4th St., El Dorado, Ks

SUBSCRIBED AND SWORN TO before me this 9th day of Sept., 1995

My Commission Expires:



Emma K. Utermoehlen
Notary Public