

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,002-0000²

LEASE NAME C. Paulsen

WELL NUMBER 2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 23 TWP. 24S RGE. 11W (E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 1-14-94

Plugging Completed 1-18-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR RAMA Operating Co., Inc.

ADDRESS Box 159 Stafford, KS 67578

PHONE#(316) 234-5191 OPERATORS LICENSE NO. 3911

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 4230'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	275'	none
				4 1/2	4180'	2402'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sanded off bottom @ 3750' & dumped 4 sks cement. Shot @ 3000' & 2402'. Worked pipe loose. Pulled all pipe. Plugged well with 300# hulls, 10 gel, 50 sks cement, 10 gel, 100# hulls, release plug, 125 sks cement, 60/40 pos 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC.

License No. 6050
STATE CORPORATION COMMISSION
RECEIVED
1-27-94

Address P. O. BOX 347 CHASE, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kelso Casing Pulling, Inc.

STATE OF KANSAS COUNTY OF RICE, ss.

CONSERVATION DIVISION
Wichita, Kansas
JAN 27 1994

R. DARRELL KELSO (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P. O. BOX 347 CHASE, KS 67524

SUBSCRIBED AND SWORN TO before me this 26th day of January, 19 94

Irene Herzberg
Notary Public

My Commission Expires:



B.J.B.
C.A.L.C.

WT

WIRE-TECH

RADIATION GUARD
LOG

ELECTRIC LOG
PROPERTY OF
BOBBY J. BEARD

COMPANY CASE OIL & GAS

WELL PAULSON #2

FIELD

COUNTY STAFFORD

STATE KANSAS

Location

Other Services:
SONIC

Sec. 23 Twp 24 Rge 11

Permanent Datum GROUND LEVEL Elev. 1807'

Elev.: K.B. 1812'

Log Measured From KELLY BUSHING 5 Ft. Above Perm. Datum

D.F.

Drilling Measured From KELLY BUSHING

G.L. 1807'

Date	5-18-84			
Run No.	ONE			
Depth—Driller	3905'			
Depth—Wire-Tech	3908'			
Btm. Log Inter.	3907'			
Top Log Inter.	2000'			
Casing—Driller	8 1/4" @ 280'	@	@	@
Casing—Wire-Tech				
Bit Size	7 3/8"			
Type Fluid in Hole	W.B. MUD			
Dens. Visc.	27 56			
pH Fluid Loss	7.0 100 ml			
Source of Sample	PIT			
R _m @ Meas. Temp.	.09 @ 80 °F	.066 @ 109 °F		
R _{ml} @ Meas. Temp.	.063 @ 80 °F	.046 @ 109 °F		
R _{mc} @ Meas. Temp.	.126 @ 80 °F	.092 @ 109 °F		
Source R _m R _{mc}	CHARTS			
R _m @BHT	.066 @ 109 °F	@ °F	@ °F	@ °F
Time Since Circ.	2 1/2 HRS.			
Max. Rec. Temp.	109 °F @ 3905'	°F @	°F @	°F @
Equip. Location	60 G.B.			
Recorded By	M. HADDON			
Witnessed By	MR. CASE & MR. FLETCHER			

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1993

CONSERVATION DIVISION
Wichita, Kansas

FIELD PRINT