

7-27-87

1 060988

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Completion Date 8/29/84

NW NW NW, SEC. 24, T 24 S, R 11 W/E

4950 feet from S section line

4950 feet from E section line

Zenith Waterflood

Lease Name Unit (ZU) Well # 27

County Stafford 126.82

Well Total Depth 3902 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 250

TECHNICIAN'S PLUGGING REPORT

Operator License # 8376

Operator: Striker Petroleum Corporation

Name & Address 5690 DTC, Suite 410

Englewood, CO 80111

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 27 Month: 7 Year: 1987

Plugging proposal received from Ronnie Hoover

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 3894' PBTD 3828' Perfs 3830-32, 3816-22' Open hole Elevation 1787' GL

1st plug sand back to 3765' and dump 5 sx cement on top of sand through bailer,

2nd plug pumped 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 125 sx cement.

Plugging Proposal Received by Richard Lacey and Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 27 Month: 7 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 3765' and dumped 5 sx cement on top of
sand through bailer,

2nd plug pumped 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2636' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

I (date) 7-29-87 observe this plugging.

DATE

7-29-87

INV. NO.

17649

JUL 29 1987

7-29-87

CONSERVATION DIVISION
Wichita, Kansas

Paul A. Luthi
(TECHNICIAN)