

1 080250

API NUMBER 15- 185-22,055-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C W/2 SW NW SEC. 24 , T 24 S, R 11 W/X  
N SE Corner of  
3300 FSL feet from ~~XXX~~ section line  
W SE Corner of  
4950 FEL feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9158

Lease Name McComb G Well # 1

Operator: Case Oil & Gas

County Stafford 125.29

Name & Address P. O. Box 341

Well Total Depth 3855 feet

Pratt, KS 67124

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 272

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 7:00 am Day: 6 Month: November Year: 19 84

Plugging proposal received from Clay Duntz

(company name) Kelso (phone) 316-938-2457

were: PBTD 3850 5 1/2" set at 3854' Perfs 3532-36' 3576-78 3791-3802'

1st plug sand back to 3480' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel 50 sx cement, 10 sx gel, 1 sack hulls, and 125 sx cement

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:00 am Day: 6 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 3854' PBTD 3850' Perfs at 3532-36' 3576-78' 3791-3802'

1st plug sanded back to 3480' and dump 5 sx cement on top of sand through bailer,

2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 125 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

11-15-84  
NOV 15 1984

Maximum pressure 300 psi and shut in pressure 50 psi

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Recovered 3000' 5 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied.  
(If additional description is necessary, use BACK of this form.)

(I did ~~not~~) observe this plugging.

Signed J. H. Metz (TECHNICIAN)

INVOICED  
DATE 11-20-84  
INV. NO. 4879