

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- - OWWO

TECHNICIAN'S PLUGGING REPORT

FEET FROM N/S SECTION LINE

FEET FROM W/E SECTION LINE

OPERATOR LICENSE # 6333

LEASE NAME Hogan WELL # 1 OWWO

OPERATOR: Alamac Drilling, Inc.
NAME & ADDRESS Box 1164
625 WASHINGTON
GREAT BEND, KS 67530

COUNTY Stafford

WELL TOTAL DEPTH 4075 \$132.44 FEET

CONDUCTOR PIPE: SIZE _____ FEET _____

SURFACE CASING: SIZE 8 5/8 FEET 255

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NUMBER 6050

ADDRESS Box 347, Chase, KS 67524

COMPANY TO PLUG AT: HOUR: 4:00pm DAY: 22 MONTH: Aug YEAR: 1983

PLUGGING PROPOSAL RECEIVED FROM Norman Veth

(COMPANY NAME) Kelso (PHONE) _____

WERE: 4 1/2" ret @ 4066' w/125 sl - Perfs 3842'-44' & 3736'-42'

3719'-24' - Sanded bottom to 3670' plus 4' sl cmt. - rec-

overed 1800' - plug well by pumping 3 sl bulls,

15 sl gel, 50 sl cmt, 10 sl gel, 1 sl bulls, release

8 5/8" plug and complete w/100 sl cmt using 60/40 Pz

w/20% gel & 3% CC PLUGGING PROPOSAL RECEIVED BY Paul Luthi (TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 4:30pm DAY: 22 MONTH: Aug YEAR: 1983

ACTUAL PLUGGING REPORT Plugged as proposed.

Max. pump pressure @ 500

Shut-in @ 300

Cementing by ALLIED

REMARKS: Elv. 1809' G.L.

RECEIVED
STATE CORPORATION COMMISSION

AUG 26 1983

CONSERVATION DIVISION
Wichita, Kansas 8-26-83

I (DID / ~~DID NOT~~) OBSERVE THIS PLUGGING.

INVOICED

DATE 8-26-83

INV. NO. 5348-W

SIGNED R. Barluttan (TECHNICIAN)