

TO:   
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-21081-00-00  
Spot: NWNWSW Sec/Twnshp/Rge: 6-24S-10W  
2310 feet from S Section Line, 5180 feet from E Section Line  
Lease/Unit Name: ZENITH UNIT Well Number: 36  
County: RENO Total Vertical Depth: 3820 feet

Operator License No.: 32699  
Op Name: ZU, LLC  
Address: 108 WEST 34TH  
HAYS, KS 67601

Production Casing Size: 5.5 feet: 3818  
Surface Casing Size: 8.625 feet: 210

\$124.15

Well Type: EOR UIC Docket No: Date/Time to Plug: 03/13/2003 1:00 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: AS PER KCC DISTRICT #2 RECOMMENDATIONS.

RECEIVED  
KCC DISTRICT #2

MAR 31 2003  
3-31-03  
WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER  
Date/Time Plugging Completed: 03/13/2003 3:15 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sand to 3400' and put 5 sx cement on top. Shoot casing off at 2000' and pull casing to 1500' and pump 35 sx. Pull casing to 950' and pump 35 sx with 50 lbs cotton hulls. Pull casing to 300' and circulate cement with 50 lbs hulls to surface.

Remarks: ALLIED CEMENT #6135 60/40 POS MIX 4% GEL.

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED

DATE 3-31-03

INV. NO. 2003061354