

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-21964-00-00
Spot: CN2NENW Sec/Twnshp/Rge: 26-24S-11W
330 feet from N Section Line, 1980 feet from W Section Line
Lease/Unit Name: MCCOMB - E Well Number: 1
County: STAFFORD Total Vertical Depth: 3908 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S. MAIN
STAFFORD, KS 67578

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 259 WITH 150 SX CMT ^{\$127.01}
Production: Size 5.5 feet: 3900 WITH 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/01/2001 12:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3850' & 5 SX CMT. 1ST PLUG AT 590' WITH 50 SX CMT. 2ND PLUG AT 289' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON
Date/Time Plugging Completed: 11/02/2001 2:00 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)
KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PBTD 3890'. PERFS AT 3584-87'. SAND BACK TO 3500' & 5 SX CMT ON TOP WITH BAILER. LOAD HOLE WITH 10 SX GEL . 1ST PLUG AT 590' WITH 50 SX CMT. 2ND PLUG AT 289' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT. GOOD CIRCULATION. HOLE STAYING FULL.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1804' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed
RECEIVED
11-5-01
NOV 05 2001
KCC WICHITA


(TECHNICIAN)

INVOICED NOV 02 2001
DATE 11-5-01
INV. NO. 2002060908 