

1 060786

API NUMBER 15-151-21,697-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SE NW, SEC. 17, T 29 S, R 15 W/E
2970 feet from S section line

TECHNICIAN'S PLUGGING REPORT

2970 feet from E section line

Operator License # 5171

Lease Name Kerr Estate "A" Well # 3

Operator: TXO Production Corporation
Name & Address 155 N. Market, Suite 1000
Wichita, KS 67202

County Pratt 160.89

Well Total Depth 4950 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 386

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Oilfield Services License Number 5105

Address 107 W. Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 2:45 pm Day: 27 Month: January Year: 19 86

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 4899' PBD 4882' Perfs at 4810-18'; 4564-72'

1st plug plug perfs with 10 sx cement

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:15 pm Day: 27 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug plugged perfs with 10 sx cement, 2nd plug squeezed well with

3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug
and pumped an additional 150 sx cement.

Maximum pressure 550 psi and shut in 350 psi

Remarks: Recovered 3032' 4 1/2" casing. Used 50/50 Pozmix by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE JAN 31 1986

Rec'd 1-31-86

Signed Paul A. Luthi
(TECHNICIAN)

INV. NO. 12223