

1 010211

FEB 2 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,615 → 00-00
C NE NE SW, SEC. 17, T 29 S, R 15 W/E
2310 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4933

Lease Name Howell Well # 1-17

Operator: Vac Petroleum Company, Inc.
Name & Address 333 North Rock Road, Suite 101
Wichita, KS 67206

County Pratt 161.30
Well Total Depth 4963 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 435

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 2 Month: 2 Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4961' PBSD 4874' Perfs at 4770-4848' Elevation 2037'GL

1st plug sand back to 4700' and dump 5 sx cement on top of cement through bailer,

2nd plug pump 5 'sx hulls and 200 sx ATL cement.

Plugging Proposal Received by Don Ubel & Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:10 p.m. Day: 2 Month: 2 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 2 sx hulls and 3 sx hulls mixed with 200 sx ATL cement.

Maximum pressure 500 psi and shut in 400 psi.

Recd 2-9-87

Remarks: Recovered 3222' of 5 1/2" casing. Used ATL cement by Allied.

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

DATE 2-10-87

Signed [Signature] FEB 9 1987
CONSERVATION DIVISION
(TECHNICIAN) Wichita, Kansas

INV. NO. 16114