

1 050664

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,727-00-00
NW NE SEC. 17, T 29 S, R 15 W
4950 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Perdue Well # 1

Operator: Raymond Oil Company Inc
Name & Address: One Main Place
Wichita KS 67202

County Pratt 173.25
Well Total Depth 4950' Arbuckle feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Aldebaran Drilling Co. Inc License Number 5829

Address 453 S. Webb Road Suite 100 Box 18611 Wichita KS 67207

Company to plug at: Hour: 6:00pm Day: 3 Month: November Year: 19 85

Plugging proposal received from Larry Harris

(company name) Aldebaran Drilling Co. Inc (phone) 316-672-7471

work: To keep hole full of good drilling mud + spot g cement plugs through drill pipe

1st plug @ base of anhydrite w/50sx

2nd plug @ 30' below base of surface w/50sx

3rd plug @ 40' w/solid bridge plug + 10sx

Circulate rathole w/15sx Plugging Proposal Received by Richard W. Lacey
Circulate mousehole w/10sx (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:00pm Day: 3 Month: November Year: 19 85

ACTUAL PLUGGING REPORT Kept hole full of good drilling mud + spotted cement plugs through drill pipe 1st plug @ 930' w/50sx

2nd plug @ 380 w/50sx

3rd plug @ 40 w/10sx

circulated Rathole w/15sx

circulated Mousehole w/10sx

circulated Waterwell w/10sx

Remarks: B.I Titan pumped 60/40 poz mix 6% gel cement
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE NOV 22 1985

INV. NO. 11149

RECEIVED
STATE CORPORATION COMMISSION
11-14-85
NOV 14 1985

Signed Richard W. Lacey
(TECHNICIAN)