

To: 1 040769 6-28  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,700 - 0D-00  
70'S of  
N NE NW W, SEC. 17, T 29 S, R 15 W EX  
400 feet from N S section line  
1650 feet from W E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 30395  
Operator: Iannitti Oil Company  
Name & Address P.O. Box 308  
Great Bend, KS 67530

Lease Name Kerr "A" Well # 4  
County Pratt  
Well Total Depth 4970 161.52 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 434

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 28 Month: 6 Year: 1993  
Plugging proposal received from Dallas

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943  
were: 5 1/2" at 4949' w/125 sx cement, PBSD 4872', Perfs at 4739-44', BP at 4955'  
1st plug sand back to 4690' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 8 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 11:30 a.m. Day: 28 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4690' and dumped 5 sx cement on top of sand  
bridge through bailer,  
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,  
100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.  
Maximum pressure 500 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 5 1/2" casing  
(if additional description is necessary, use BACK of this form.)

**INVOICED**  
I (did / did not) observe this plugging.  
DATE: 7-7-93  
INV. NO. 38058

Signed Stephen J. Pfeifer  
(TECHNICIAN)  
RECEIVED  
STATE CORP  
7-6-93  
JUL - 6 1993  
Wichita Falls