

1 040042

1-22-88

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,682 -00-00
SE NW NW, SEC. 17, T 29 S, R 15 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Operator: TXO Production Corp.
Name & Address 125 North Market, Suite 1000
Wichita, KS 67202

4290 feet from S section line
4290 feet from E section line

Lease Name Kerr Estate "A" Well # 2
County Pratt 158.93

Well Total Depth 4890 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 431

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers Inc. License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 8:15 a.m. Day: 22 Month: 1 Year: 19 88

Plugging proposal received from Allen Dick

(company name) TXO Production Corporation (phone) 316-886-5605

were: 5 1/2" at 4889' PBSD 4869' Perfs at 4792-4802'

1st plug sand back to 4750' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9 a.m. Day: 22 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4750' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 100 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 1000 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2100' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (void / XXXXXX) observe this plugging.

DATE 1-28-88

INV. NO. 19901

Signed Stephen J. Pfeifer (TECHNICIAN)