

1 040043

1-22-88

API NUMBER 15- 151-21,662 - 00.00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW NW, SEC. 17, T 29 S, R 15 (W)E

4950 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Kerr Estate "A" Well # 1

Operator: TXO Production Corporation
Named
Address 125 North Market, Suite 1000
Wichita, KS 67202

County Pratt 159.93

Well Total Depth 4921 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 371

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers Inc. License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 22 Month: 1 Year: 19 88

Plugging proposal received from Allen Dick

(company name) TXO Production Corporation (phone) 316-886-5605

were: 5 1/2" at 4920' PBD 4907' Perfs at 4800-10'

1st plug sand back to 4750' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:30 a.m. Day: 22 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4750' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 800 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2900' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form)

RECEIVED
STATE CORPORATION COMMISSION
1-27-88
JAN 27 1988

INVOICED (to be filled in by contractor) observe this plugging.

Signed Stephen J. Pfeiffer
(TECHNICIAN)

DATE 1-28-88

INV. NO. 19702