

To: 1 051371
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-28 15,151-21616-60-60

API NUMBER 15- NA
NE/4
SEC. 18, T. 29 S, R 15 W/E
feet from S section line
feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3399

Lease Name Howell Well # 1-18

Operator: Farrar Pump & Supply, Inc.
Name &
Address P.O. Box 209
Medicine Lodge, KS 67104

County Pratt 172.31
Well Total Depth 5302 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 450

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 1 p.m. Day: 28 Month: 11 Year: 19 90

Plugging proposal received from Judy Barry

(company name) Pratt Well Service (phone) 316-672-2531

were: 5 1/2" at 5154' w/225 sx cement, PBTD 4780', Perfs at 4752-56'

1st plug sand back to 4700' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 28 Month: 11 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4500' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 600 psi and shut in 400 psi.

RECEIVED
RECEIVED
STATE CORPORATION COMMISSION
Rec'd 12-4-90

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3155' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

(Add XXXXX) observe this plugging.

INVOICED

Signed Richard W. Gray
(TECHNICIAN)

DATE 12-7-90

INV. NO. 30189