

1 080454

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,661-00-00

NW NE NE, SEC. 18, T 29 S, R 15 W/E

4950 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8625

Lease Name Howell Well # 3-18

Operator: Vac Petroleum Company

County Pratt 161.20

Name & Address 333 North Rock Road, Suite 105

Well Total Depth 4960 feet

Wichita, KS 67206

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 448

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pulling, Inc. License Number 4635

Address P. O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 12:15 pm Day: 25 Month: November Year: 19 85

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pulling (phone) 316-793-9711

were: 5 1/2" at 4957' PBTD 4950' Perfs at 4796-4812'; 4848-52'; 4698-4710'

1st plug sand back to 4650' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 120 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:40 pm Day: 25 Month: November Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4650' and dumped 5 sx cement on top of sand through dump bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 120 sx cement.

Maximum pressure 500 psi and shut in 100 psi

Remarks: Recovered 3021' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 10 1985

INV. NO. 11389

RECEIVED

STATE CORPORATION COMMISSION Signed

DEC 5 1985

12-5-85 CONSERVATION DIVISION Wichita, K.

J. H. [Signature] (TECHNICIAN)